BRUHAT BANGALORE MAHANAGARA PALIKE

Item No.37

APPROVED SCHEDULE - B

Tender Notification No: BBMP/ EE /Btp/Ten/05/2012-13 Dated: 30-07-2012

Name of Work: Construction of culverts and drains in Kalapp Layout, Muneshwara Layout and Gopalappa Garden in ward no 10 Doddabommasandra.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S. NARAYANASWAMY	
				In Figures	In Words
1	27.14	Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50 m and removing the debris to a distance upto 200m,	Cum	**130.00**	Rupees One Hundred Thirty Only
2	192.96	KSRRB 300-2 : Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3	Sqm	**80.00**	Rupees Eighty Only
3	165.83	Removing B.S Slab of Drain and stacking	Cum	**45.00**	Rupees Forty Five Only
4	36.18	Providing and laying in position **plain cement concrete of nominal mix 1:4:8 using 40mm** and down size graded granite metal machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification	Sqm	**4050.00**	Rupees Four Thousand Fifty Only
5	8.14	KSRB 5.2-2 Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6,** stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Sqm	**2000.00**	Rupees Two Thousand Only
6	72.66	Providing and constructing granite / trap / basalt size stone masonry in **basement with cement mortar 1:6**, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	**3200.00**	Rupees Three Thousand Two Hundred Only
7	19.60	KSRB 4-1.7 : Providing and laying in position **plain cement concrete of nominal mix 1:2:4 using 20mm** and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification.	Cum	**4650.00**	Rupees Four Thousand Six Hundred Fifty Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S. NARAYANASWAMY	
				In Figures	In Words
8	120.60	KSRB 15.1.1: Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Cum	**69.00**	Rupees Sixty Nine Only
9	79.35	KSRB 4-6.2 Providing and removing centering, shuttering, strutting, propping etc.,and removal of form work for all flat syrface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200mm including cost of all materials, labour complete as per specifications.	Cum	**245.00**	Rupees Two Hundred Forty Five Only
10	45.07	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of nominal mix 1:1.5:3 with 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification	Cum	**5450.00**	Rupees Five Thousand Four Hundred Fifty Only
11	40.57	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.	Sqm	**5900.00**	Rupees Five Thousand Nine Hundred Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92